



REPUBLIC OF KENYA
COUNTY GOVERNMENT OF LAMU



DEPARTMENT OF LANDS, HOUSING, INFRASTRUCTURE & URBAN DEVELOPMENT
PUBLIC WORKS DEPARTMENT

BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI CATTLE DIP

TENDER NO. CGL/ONT/LIVSCO/014/2018-2019

ISSUED ON: 23RD JANUARY, 2019

SUBMISSION DEADLINE: WEDNESDAY 13TH FEBRUARY, 2019 AT 10.00 A.M.
LOCAL TIME

January, 2019

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p align="center">PARTICULAR PRELIMINARIES</p> <p>PRICING OF ITEMS OF PRELIMINARIES</p> <p>Items described in this section cover the minimum requirements and conditions necessary for the full and proper execution of the contract. The tenderer is required to read and fully understand his obligations under each item and thus assess his costs for complying with the same for the duration of the contract. Should no price be inserted against any item, it shall be assumed that the tenderer has covered any costs associated with that item elsewhere in the Bills of quantities and shall nevertheless be required to comply with such and all items of preliminaries.</p> <p><u>TENDER VALIDITY</u></p> <p>The attention of the Tenderers is drawn to clause 3.6 and 3.8 of Conditions of Contract on validity of tender and Tender Security.</p> <p>VALUE ADDED TAX (VAT) AND OTHER TAXES</p> <p>All prices will be inclusive of all statutory taxes and levies, including VAT, necessary for the complete and proper execution of that particular item of the works including complying with all statutory requirements. The amount of VAT payable will be deducted from every payment certified by the Project Manager and paid directly to the Commissioner of VAT.</p> <p>SCOPE OF CONTRACT</p> <p>The work to be carried out under this contract comprises of Cattle Dip together with the associated works for the Department of Veterinary & Livestock as described in these Bills of Quantities and in accordance with the contract drawings and any other drawings which may be issued in amplification thereof.</p> <p>DESCRIPTION OF THE WORKS</p> <p>The works generally comprise of IT roofing Sheets on steel trusses.</p> <p>The floors are finished in cement sand screeds while the walls are plastered and painted.</p> <p>FLOOR AREAS</p> <p>The gross floor area is 82 Square Meters. The overall floor area is measured over walls and is given without warranty but for guidance only.</p> <p>LOCATION OF SITE</p> <p>The site for the works is located in Witu Ward. The tenderer shall be deemed to have visited the site and familiarised himself with all site conditions prior to submission of tenders.</p> <p>EXISTING BUILDINGS</p> <p>Special precautions shall be required throughout the contract period to avoid damage to the existing structures, roads, lawns, cables, drains and other services.</p> <p>The Contractor shall allow for making good any damage arising from his actions during execution of this contract at his own expense.</p>	
	CARRIED TO COLLECTION PAGE: PARTICULAR PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>GENERAL</p> <p>The contractor is referred to the General Specifications for Building Works 1976 Edition and must allow for all costs in complying with these specifications.</p> <p>CONTRACT COMPLETION PERIOD</p> <p>The contract completion period in accordance with Clause 31 of the conditions of contract must be strictly adhered to. The "PROJECT MANAGER" shall strictly monitor the Contractor's progress in relation to the progress chart and should it be found necessary, the "PROJECT MANAGER" shall inform the Contractor in writing that his actual performance on site is not satisfactory. In all such cases, the Contractor shall accelerate his rate of performance, production and progress by all means such as additional labor, plant etc. and working overtime all at his cost.</p> <p>PARTICULARS OF INSERTIONS TO BE MADE IN THE APPENDIX TO CONTRACT AGREEMENT</p> <p>The following are insertions to be made in the appendix to the Contract Agreement.</p> <p>(i) Period of final measurement - 6 Months from practical completion date [Condition 32]</p> <p>(ii) Defects Liability Period - 6 Months from practical completion date [Condition 20]</p> <p>(iii) Date for Possession - To be agreed with "PROJECT MANAGER" [Condition 14]</p> <p>(iv) Date of Completion - To be agreed with "PROJECT MANAGER" [Condition 31]</p> <p>(v) Liquidated and Ascertained Damages Clause 24 - At the rate of Kshs.20,000/= per week or part thereof [Condition 27]</p> <p>(vi) Period of Interim Certificates - Monthly [Condition 23]</p> <p>(vii) Period of Honoring Certificates - Thirty (30) Days [Condition 23]</p> <p>(viii) Percentage of Certified value retained - 10% [Condition 26]</p> <p>(ix) Limit of retention fund - 5% [Condition 26]</p> <p>(x) Bond - The Bond required shall be from an approved bank ONLY [Condition 28]</p> <p>PROJECT MANAGEMENT EXPENSES</p> <p>Allow for project management expenses including transport, airtime and Lunches to be used as directed by the Project Manager or deducted in whole or in part as the case may be.</p>	
	CARRIED TO COLLECTION PAGE: PARTICULAR PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>LABOUR CAMPS</p> <p>The Contractor shall not be permitted to house labor on the site and he must take full responsibility for transporting labour daily to and from the site as required and the cost of this shall be included in his tender.</p> <p>OFFICE FOR THE "PROJECT MANAGER"</p> <p>The site office mentioned in item B page GP/7 of the General Preliminaries shall be type "B" as shown on the Ministry of Works Standard Detail. The contractor shall insure the office and furniture against fire, theft and natural calamities and provided day and night security. He shall also provide and maintain adequate access and parking acceptable to the PROJECT MANAGER.</p> <p>TELEPHONE</p> <p>The contractor shall provide telephone facilities (fixed or mobile) on site throughout the duration of the contract for use by the Project Manager. He shall also maintain the phone in permanent working condition and pay all charges for the duration of the Contract.</p> <p>SIGN BOARD</p> <p>Allow for providing, erecting, maintaining throughout the course of the contract and after clearing away a signboard as designed, specified and approved by the Project Manager.</p> <p>HOARDING</p> <p>Hoarding shall not be erected</p> <p>PROGRAMME PROGRESS CHART</p> <p>The Contractor shall allow for providing within One (1) week after the date of possession of the site and in agreement with the "PROJECT MANAGER" a progress chart for the whole of the works. One copy shall be forwarded to the "PROJECT MANAGER" and another copy shall be retained on site on which progress shall be recorded by the Contractor. Should any circumstance arise affecting the program or progress, the chart shall be modified as necessary in consultation with the "PROJECT MANAGER".</p> <p>PERFORMANCE SECURITY (BOND)</p> <p>The Contractor should note that the Performance Security to be provided must be in form of a bank guarantee in the amount of 5 % of the Contract Sum. The form to be signed is M.O.W. 118 or any other format acceptable to the Employer.</p> <p>PAYMENTS TO DOMESTIC SUBCONTRACTORS</p> <p>The Main Contractor shall be fully responsible for paying his Domestic Sub -Contractors but the Government reserves the right in very exceptional circumstances to make such payments direct in the interest of the project, where completion thereof might be jeopardised by any dispute between any of the Contractors and Sub -Contractors involved.</p> <p>APPENDICES</p> <p>The Appendices to the Bills of Quantities shall be regarded for contract purposes as part of the Bill and shall be read and construed with the appropriate sections of the Bills if contained therein.</p>	
	CARRIED TO COLLECTION PAGE: PARTICULAR PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>SUFFICIENCY OF TENDER</p> <p>The main Contractor shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for the works and of the rates and prices stated in the Bills of Quantities which rates and prices shall cover all his obligations under the contract and all matters and things necessary for the proper completion of the works.</p> <p>GENERAL SPECIFICATIONS</p> <p>For the full description of materials ,workmanship and method of execution of the works, the Contractor is referred to the Ministry of Works General specifications for building works dated 1976 or any subsequent revision thereof which is issued as a separate document and which shall be followed in all respects unless it conflicts with the General and Particular Preliminaries, Trade Preambles or other items in these Bills of Quantities. In the event of such conflict, then the provisions of the General and Particular Preliminaries, Trade Preambles and these Bills of Quantities take precedence.</p> <p>TRAINING LEVY</p> <p>The Contractor's attention is drawn to Legal Notice No. 237 of October 1971 which requires payment by the Contractor of a Training levy at the rate of 1/4 % of the Contract Sum on all Contracts of more than Kshs. 50,000.00 in value.</p> <p>MATERIALS ON SITE</p> <p>All materials for incorporation in the works must be stored on or adjacent to the site of the works before payment is effected by the "PROJECT MANAGER". This is to include the materials of the Main Contractor, Sub - contractors and Nominated Suppliers.</p> <p>SECURITY AND ACCESS TO THE SITE</p> <p>The Contractor must include in his tender for all necessary expenditure incurred in complying with the security regulations of the Department of Veterinary & Livestock especially in relation to entry and exit from the site of the works and movement within the site.</p> <p>SECURITY</p> <p>The Contractor shall be responsible for ensuring that all personnel of non-Kenyan origin employed on site by himself or his sub-contractors or who are otherwise connected with the construction of contract through the Contractor must be approved and cleared to work on the project individually in writing by the relevant Government Agencies.</p> <p>Where personnel are not approved, the Contractor shall be responsible at his own expense for obtaining and employing suitable and approved personnel.</p> <p>The Contractor shall be responsible for ensuring that all matters including drawings, letters and documentation relating to the project are dealt with confidentiality.</p> <p>He will be expected to post notices on site instructing his employees to treat all matters relating to the project as confidential.</p> <p>NUISANCE</p> <p>The Contractor shall not directly or indirectly or otherwise by himself or through his agents cause nuisance . Should he do so he shall be directly responsible for such acts.</p>	
	CARRIED TO COLLECTION PAGE: PARTICULAR PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>COLLECTION PAGE: PARTICULAR PRELIMINARIES</p> <p>Balance brought forward from page DISP/1</p> <p>Balance brought forward from page DISP/2</p> <p>Balance brought forward from page DISP/3</p> <p>Balance brought forward from page DISP/4</p>	
	Total for Particular Preliminaries Carried to Summary Page (PRELIMINARIES)	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p align="center">GENERAL PRELIMINARIES</p> <p>PRICING OF ITEMS OF PRELIMINARIES AND PREAMBLES</p> <p>No Prices will be inserted against items of Preliminaries and Preambles in the Contractor's priced Bills of Quantities and Specification. The Contractor shall be deemed to have included in his prices or rates for the various items in the Bills of Quantities or Specification for all costs involved in complying with all the requirements for the proper execution of the whole of the works in the Contract.</p> <p>ABBREVIATIONS</p> <p>Throughout these Bills, units of measurement and terms are abbreviated and shall be interpreted as follows:-</p> <p>C.M. Shall mean cubic metre</p> <p>S.M. Shall mean square metre</p> <p>L.M. Shall mean linear metre</p> <p>mm Shall mean Millimetre</p> <p>KG Shall mean Kilogramme</p> <p>No. Shall mean Number</p> <p>PRS. Shall mean Pairs</p> <p>B.S. Shall mean the British Standard Specification Published by the British Standards Institution, 2 Park Street, London W.I., England.</p> <p>ditto Shall mean the whole of the preceding description except as qualified in the description in which it occurs.</p> <p>m.s. Shall mean measured separately.</p> <p>a. b. d Shall mean as before described</p> <p>EXCEPTION TO THE STANDARD METHOD OF MEASUREMENT</p> <p><u>Attendance</u> Clause B19(a) of the Standard Method of Measurement is deleted and the following clause is substituted:-</p> <p>Attendance on nominated Sub-Contractors shall be given as an item in each case shall be deemed to include: allowing use of standing scaffolding, mess rooms, sanitary accommodation and welfare facilities; provision of special scaffolding where necessary; providing space for office accommodation and for storage of plant and materials; providing light and water for their work; clearing away rubbish; unloading checking and hoisting; providing electric power; and removing and replacing duct covers, pipe casings and the like necessary for the execution and testing of Sub- Contractors' work and being responsible for the accuracy of the same.</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>Fix Only:-</p> <p>"Fix Only" shall mean take delivery at nearest railway station (Unless otherwise stated), pay all demurrage charges, load and transport to site where necessary, unload, store, unpack, assemble as necessary, distribute to position, hoist and fix only.</p> <p>EMPLOYER</p> <p>The Employer is the County Government of Lamu. The terms "Employer" and "County Government" whoever used in any contract document shall be synonymous.</p> <p>PROJECT MANAGER</p> <p>The term "Project Manager." wherever used in these Bills of Quantities shall be deemed to imply the Project Manager as defined in Condition 1 of the Conditions of Contract or such person or persons as may be duly authorized to represent him on behalf of the County Government.</p> <p>FORM OF CONTRACT</p> <p>The form of contract will be the one included in the Republic of Kenya Standard Tender Documents for Procurements of Works (2000 Edition) hereby attached and the Conditions of Contract are those attached thereto. If the contractor considers that the compliance with any of the Conditions of Contract involves any expenses he will distribute them among his rates for the various items in the Bills of Quantities. No claim shall be allowed arising from the Contractors Compliance with any of the conditions of Contract. These are numbered from 1 to 26 as set out on pages 18 to 27 of these tender Documents. Particulars of the insertions to be made in the Appendix of the Contract Agreement will be found in the Particular Preliminaries of these Bills Of Quantities.</p> <p>BOND.</p> <p>The Contractor shall find and submit on the Form of Tender the name of one surety who shall be an approved bank and who will be willing to be bound to the County Government of Lamu in and amount equal to Five percent (5%) of the Contract amount for the due performances of the Contract up to the date of completion as certified by the PROJECT MANAGER and who will when and if called upon sign a Bond to that effect on Ministry of Public Works Form No. 118 (without the addition of any limitations).</p> <p>PLANT, TOOLS AND VEHICLES</p> <p>Allow for providing all scaffolding, plant, tools and vehicles required for the works except in so far as may be stated otherwise herein and except for such items specifically and only required for the use of nominated Sub-Contractors as described herein. No timber used for scaffolding, formwork or temporary works of any kind shall be used afterwards in the permanent work.</p> <p>TRANSPORT.</p> <p>Allow for transport of workmen, materials, etc., to and from the site at such hours and by such routes as may be permitted by the competent authorities.</p> <p>MATERIALS AND WORKMANSHIP.</p> <p>All materials and workmanship used in the execution of the work shall be of the best quality and description unless otherwise stated. The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that they are on site when required for use in the works. The Bills of Quantities shall not be used for the purpose of ordering materials.</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>SIGN FOR MATERIALS SUPPLIED.</p> <p>The Contractor will be required to sign a receipt for all articles and materials supplied by the PROJECT MANAGER at the time of taking deliver thereof, as having received them in good order and condition, and will thereafter be responsible for any loss or damage and for replacements of any such loss or damage with articles and/or materials which will be supplied by the "PROJECT MANAGER" at the current market prices including Customs Duty and V.A.T., all at the Contractor's own cost and expense, to the satisfaction of the "PROJECT MANAGER"</p> <p>STORAGE OF MATERIALS</p> <p>The Contractor shall provide at his own risk and cost where directed on the site weatherproof lockup sheds and make good damaged or disturbed surfaces upon completion to the satisfaction of the PROJECT MANAGER Nominated Sub-Contractors are to be made liable for the cost of any storage accommodation provided especially for their use.</p> <p>SAMPLES</p> <p>The Contractor shall furnish at his own cost any samples of materials or workmanship including concrete test cubes required for the works that may be called for by the PROJECT MANAGER for his approval until such samples are approved by the PROJECT MANAGER and the PROJECT MANAGER, may reject any materials or workmanship not in his opinion to be up to approved samples. The PROJECT MANAGER shall arrange for the testing of such materials as he may at his discretion deem desirable, but the testing shall be made at the expense of the Contractor and not at the expense of the PROJECT MANAGER. The Contractor shall pay for the testing in accordance with the current scale of testing charges laid down by the Ministry of Roads and Public Works. The procedure for submitting samples of materials for testing and the method of marking for identification shall be as laid down by the PROJECT MANAGER. The Contractor shall allow in his tender for such samples and tests except those in connection with nominated sub-contractors' work.</p> <p>GOVERNMENT ACTS REGARDING WORKPEOPLE ETC.</p> <p>Allow for complying with all Government Acts, Orders and Regulations in connection with the employment of Labour and other matters related to the execution of the works. In particular the Contractor's attention is drawn to the provisions of the Factory Act 1950 and his tender must include for all costs arising or resulting from compliance with any Act, Order or Regulation relating to Insurances, pensions and holidays for workpeople or so the safety, health and welfare of the workpeople. The Contractor must make himself fully acquainted with current Acts and Regulations, including Police Regulations regarding the movement, housing, security and control of labor, labor camps, passes for transport, etc. It is most important that the Contractor, before tendering, shall obtain from the relevant Authority the fullest information regarding all such regulations and/or restrictions which may affect the organization of the works, supply and control of labor, etc. And allow accordingly in his tender. No claim in respect of want of knowledge in this connection will be entertained.</p> <p>SECURITY OF WORKS ETC.</p> <p>The Contractor shall be entirely responsible for the security of all the works stores, materials, plant, personnel, etc., both his own and sub-contractors' and must provide all necessary watching, lighting and other precautions as necessary to ensure security against theft, loss or damage and the protection of the public.</p> <p>PUBLIC AND PRIVATE ROADS.</p> <p>Maintain as required throughout the execution of the works and make good any damage to public or private roads arising from or consequent upon the execution of the works to the satisfaction of the local and other competent authority and the PROJECT MANAGER</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>EXISTING PROPERTY.</p> <p>The Contractor shall take every precaution to avoid damage to all existing property including roads, cables, drains and other services and he will be held responsible for and shall make good all such damage arising from the execution of this contract at his own expense to the satisfaction of the PROJECT MANAGER.</p> <p>VISIT SITE AND EXAMINE DRAWINGS.</p> <p>The Contractor is recommended to examine the drawings and visit the site the location of which is described in the Particular Preliminaries hereof. He shall be deemed to have acquainted himself therewith as to its nature, position, means of access or any other matter which may affect his tender. No claim arising from his failure to comply with this recommendation will be considered.</p> <p>ACCESS TO SITE AND TEMPORARY ROADS.</p> <p>Means of access to the Site shall be agreed with the PROJECT MANAGER prior to commencement of the work and Contractor must allow for building any necessary temporary access roads for the transport of the materials, plant and workmen as may be required for the complete execution of the works including the provision of temporary culverts, crossings, bridges, or any other means of gaining access to the Site. Upon completion of the works, the Contractor shall remove such temporary access roads; temporary culverts, bridges, etc., and make good and reinstate all works and surfaces disturbed to the satisfaction of the "PROJECT MANAGER".</p> <p>AREA TO BE OCCUPIED BY THE CONTRACTOR</p> <p>The area of the site which may be occupied by the Contractor for use of storage and for the purpose of erecting workshops, etc., shall be defined on site by the "PROJECT MANAGER"</p> <p>OFFICE ETC. FOR THE PROJECT MANAGER</p> <p>The Contractor shall provide, erect and maintain where directed on site and afterwards dismantle the Site Office of the type noted in the Particular Preliminaries, complete with furniture .He shall also provide a strong metal trunk complete with strong hasp and staple fastening and two keys. He shall provide, erect and maintain a lock-up pedestal type water or bucket closet for the sole use of the PROJECT MANAGER including making temporary connections to the drain where applicable to the satisfaction of Government and Medical Officer of Health and shall provide the services of cleaner and pay all conservancy charges and keep both office and closet in a clean and sanitary condition from the commencement to the completion of the works and dismantle and make good disturbed surfaces. The office and closet shall be completed before the Contractor is permitted to commence the works. The Contractor shall make available on the Site as and when required by thebe the PROJECT MANAGER a modern and accurate level together with leveling staff, ranging rods and 50 meter metallic or linen tape.</p> <p>WATER AND ELECTRICITY SUPPLY FOR THE WORKS</p> <p>The Contractor shall provide at his own risk and cost all necessary water, electric light and power required for use in the works. The Contractor must make his own arrangements for connection to the nearest suitable water main and for metering the water used. He must also provide temporary tanks and meters as required at his own cost and clear away when no longer required and make good on completion to the entire satisfaction of the PROJECT MANAGER. The Contractor shall pay all charges in connection herewith. No guarantee is given or implied that sufficient water will be available from mains and the Contractor must make his own arrangements or augmenting this supply at his own cost. Nominated sub-contractors are to be made liable for the cost of any water or electric current used and for any installation provided especially for their own use.</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>SANITATION OF THE WORKS</p> <p>The Sanitation of the works shall be arranged and maintained by the Contractor to the satisfaction of the Government and/or Local Authorities, Labor Department and the PROJECT MANAGER</p> <p>SUPERVISION AND WORKING HOURS</p> <p>The works shall be executed under the direction and to the entire satisfaction in all respects of the PROJECT MANAGER who shall at all times during normal working hours have access to the works and to the yards and workshops of the Contractor and sub-Contractors or other places where work is being prepared for the contract. The working hours shall be those generally worked by good employees in the Building and Civil Engineering trades in Kenya .No work shall be carried out at night or on gazzeted holidays unless the PROJECT MANAGER shall direct so. No work shall be covered up nor shall any concreting be carried out in the absence of the Clerk of Works without prior approval of the PROJECT MANAGER in writing.</p> <p>PROVISIONAL SUMS.</p> <p>The term "Provisional Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7(i) of the Standard Method of Measurement Such sums are net and no addition shall be made to them for profit.</p> <p>PRIME COST (OR P.C.) SUMS.</p> <p>item A7 (ii) of the Standard Method of Measurement. Persons or firms nominated by the PROJECT MANAGER to execute</p> <p>PROGRESS CHART.</p> <p>The Contractor shall provide within two weeks of Possession of Site and in agreement with the PROJECT MANAGER a Progress Chart for the whole of the works including the works of Nominated Sub- Contractors ; one copy to be handed to the PROJECT MANAGER and a further copy to be retained on Site. Progress to be recorded and chart to be amended as necessary as the work proceeds.</p> <p>ADJUSTMENT OF P.C. SUMS.</p> <p>In the final account all P.C. Sums shall be deducted and the amount properly expended upon the D.R's order in respect of each of them added to the Contract sum. The Contractor shall produce to the PROJECT MANAGER such quotations, invoices or bills, properly receipted, as may be necessary to show the actual details of the sums paid by the Contractor. Items of profit upon P.C. Sums shall be adjusted in the final account pro-rata to the amount paid. Items of "attendance" (as previously described) following P.C. Sums shall be adjusted pro-rata to the physical extent of the work executed (not pro-rata to the amount paid) and this shall apply even though the Contractor's priced Bill shows a percentage in the rate column in respect of them. Should the Contractor be permitted to tender and his tender be accepted of any work for which a P.C. Sum is included in these Bill of Quantities profit and attendance will be allowed at the same rate as it would be if the work were executed by a Nominated Sub-Contractor.</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>ADJUSTMENT OF PROVISIONAL SUMS.</p> <p>In the final account all Provisional Sums shall be deducted and the value of the work properly executed in respect of them upon the PROJECT MANAGER's order added to the Contract Sum. Such work shall be valued as described for Variations in Conditions No. 22 of the Conditions of Contract, but should any part of the work be executed by a Nominated Sub-Contractor, the value of such work or articles for the work to be supplied by a Nominated Supplier, the value of such work or articles shall be treated as a P.C. Sum and profit and attendance comparable to that contained in the priced Bills of Quantities for similar items added.</p> <p>NOMINATED SUB-CONTRACTORS</p> <p>When any work is ordered by the PROJECT MANAGER to be executed by nominated sub-contractors, the Contractor shall enter into sub-contracts as described in Condition No. 20 of the Conditions of Contract and shall thereafter be responsible for such sub-contractors in every respect. Unless otherwise described the Contractor is to provide for such Sub-Contractors any or all of the facilities described in these Preliminaries. The Contractor should price for these with the nominated Sub-contract Contractor's work concerned in the P.C. Sums under the description "add for Attendance".</p> <p>DIRECT CONTRACTS</p> <p>Notwithstanding the foregoing conditions, the County Government reserves the right to place a "Direct Contract" for any goods or services required in the works which are covered by a P.C. Sum in the Bills of Quantities and to pay for the same direct. In the instances, profit relative to the P.C. Sum the priced Bills of Quantities will be adjusted as described for P.C. Sums and allowed.</p> <p>ATTENDANCE UPON OTHER TRADESMEN, ETC.</p> <p>The Contractor shall allow for the attendance of trade upon trade and shall afford any tradesmen or other persons employed for the execution of any work not included in this Contract every facility for carrying out their work and also for use of his ordinary scaffolding. The Contractor, however, shall not be required to erect any special scaffolding for them. The Contractor shall perform such cutting away for and making good after the work of such tradesmen or persons as may be ordered by the PROJECT MANAGER and the work will be measured and paid for to the extent executed at rates provided in these Bills.</p> <p>INSURANCE</p> <p>The Contractor shall insure as required in Conditions Nos. 22 and 23 of the Conditions of Contract. No payment on account of the work executed will be made to the Contractor until he has satisfied the PROJECT MANAGER either by production of an Insurance Policy or and Insurance Certificate that the provision of the foregoing Insurance Clauses have been complied with in all respects. Thereafter the PROJECT MANAGER shall from time to time ascertain that premiums are duly paid up by the Contractor who shall if called upon to do so, produce the receipted premium renewals for the PROJECT MANAGER's inspection.</p> <p>PROVISIONAL WORK</p> <p>All work described as "Provisional" in these Bills of Quantities is subject to re-measurement in order to ascertain the actual quantity executed for which payment will be made. All "Provisional" and other work liable to adjustment under this Contract shall left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the PROJECT MANAGER Immediately the work is ready for measuring, the Contractor shall give notice to the PROJECT MANAGER. If the Contractor makes default in these respects he shall if the PROJECT MANAGER so directs uncover the work to enable all measurements to be taken and afterwards reinstate at his own expense.</p>	
	CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>ALTERATIONS TO BILLS, PRICING, ETC.</p> <p>Any unauthorized alteration or qualification made to the text of the Bills of Quantities may cause the Tender to be disqualified and will in any case be ignored. The Contractor shall be deemed to have made allowance in his prices generally to cover any items against which no price has been inserted in the priced Bills of Quantities. All items of measured work shall be priced in detail and the Tenders containing Lump Sums to cover trades or groups of work must be broken down to show the price of each item before they will be accepted.</p> <p>BLASTING OPERATIONS</p> <p>Blasting will only be allowed with the express permission of the PROJECT MANAGER in writing. All blasting operations shall be carried out at the Contractor's sole risk and cost in accordance with any Government regulations laid down by the PROJECT MANAGER governing the use and storage of explosives.</p> <p>MATERIALS ARISING FROM EXCAVATIONS</p> <p>MANAGER directs otherwise such materials shall be dealt with as provided in the Contract. Such materials shall only be used</p> <p>PROTECTION OF THE WORKS.</p> <p>Provide protection of the whole of the works contained in the Bills of Quantities, including casing , casing up, covering or such other means as may be necessary to avoid damage to the satisfaction of the PROJECT MANAGER and remove such protection when no longer required and make good any damage which may nevertheless have been done at completion free of cost to the Government.</p> <p>REMOVAL OF RUBBISH ETC.</p> <p>Removal of rubbish and debris from the Buildings and site as it accumulates and at the completion of the works and remove all plant, scaffolding and unused materials at completion.</p> <p>WORKS TO BE DELIVERED UP CLEAN</p> <p>Clean and flush all gutters, rainwater and waste pipes, manholes and drains, wash (except where such treatment might cause damage) and clean all floors, sanitary fittings, glass inside and outside and any other parts of the works and remove all marks, blemishes, stains and defects from joinery, fittings and decorated surfaces generally, polish door furniture and bright parts of metalwork and leave the whole the buildings watertight, clean, perfect and fit for occupation to the approval of the PROJECT MANAGER</p> <p>GENERAL SPECIFICATION.</p> <p>For the full description of materials and workmanship, method of execution of the work and notes for pricing, the Contractor is referred to the Ministry of Roads and Public Works General Specification dated 1976 or any subsequent revision thereof which is issued as a separate document, and which shall be allowed in all respects, unless it conflicts with the General Preliminaries, Trade Preambles or other items in these Bills of Quantities.</p> <p>TRAINING LEVY</p> <p>The Contractor's attention is drawn to legal notice No. 237 of October, 1971, which requires payment by the Contractor of a Training Levy at the rate of 1/4 % of the Contract sum on all contracts of more than Kshs. 50,000.00 in value.</p> <p>MATERIALS ON SITE</p> <p>All materials for incorporation in the works must be stored on or adjacent to the site before payment is effected unless specifically exempted by the PROJECT MANAGER. This is to include the materials of Main Contractor, Nominated Sub-Contractors and Nominated Suppliers.</p>	
	<p>CARRIED TO COLLECTION PAGE: GENERAL PRELIMINARIES</p>	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>COLLECTION PAGE: GENERAL PRELIMINARIES</p> <p>Brought forward from page DISP/6</p> <p>Brought forward from page DISP/7</p> <p>Brought forward from page DISP/8</p> <p>Brought forward from page DISP/9</p> <p>Brought forward from page DISP/10</p> <p>Brought forward from page DISP/11</p> <p>Brought forward from page DISP/12</p>	
	Total for General Preliminaries Carried to Summary Page (PRELIMINARIES)	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

ITEM	DESCRIPTION	AMOUNT
	<p>SUMMARY PAGE: PRELIMINARIES</p> <p>Balance brought forward from page DISP/5</p> <p>Balance brought forward from page DISP/13</p>	
	Total for Preliminaries Carried to Grand Summary	

**BILL OF QUANTITIES FOR CONSTRUCTION OF KITUMBINI
CATTLE DIP**

PROPOSED KITUMBINI CATTLE DIP

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>EXCAVATION</u>				
A.	Excavate oversite average 200mm deep and cart away	SM	59		
B.	Excavate basement not exceeding 1.5m deep	CM	58		
C.	Ditto 1.5-3.0m deep	CM	18		
D.	Extra-over excavation for excavating in rock	CM	60		
E.	Cart away excavated material from site	CM	76		
F.	Allow for planking & strutting sides of excavations	ITEM	1		
G.	Allow for keeping excavations free from water	ITEM	1		
H.	300mm Thick approved hardcore	SM	44		
	<u>REINFORCED CONCRETE (1:2:4)IN:-</u>				
I.	150mm surface bed.	SM	44		
J.	Retaining walls	CM	6		
K.	Steps	CM	2		
L.	Ground beams	CM	2		
CARRIED TO COLLECTION					

PROPOSED KITUMBINI CATTLE DIP

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>SAWN FORMWORK TO:</u>				
A	Sides of retaining walls	SM	58		
B	Sides and soffites of ground beam	SM	7		
C	Edges of steps 75-150mm high	LM	39		
	<u>HIGH YIELD REINFORCEMENT BARS</u>				
D	8mm diameter bars	KG	2560		
E	10mm Ditto	KG	1500		
F	12mm ditto	KG	820		
	BRC Mesh				
G	BRC mesh type A-142	SM	9		
	Walling				
H	200mm masonry walling in cementsand(1;3)mortar	SM	34		
	Plaster				
I	15mm thick cement sand (1:3) plaster on walling	SM	34		
	<u>ROOFING</u>				
J	100X50mm sawn treatedcypress rafters	LM	78		
CARRIED TO COLLECTION					

PROPOSED KITUMBINI CATTLE DIP

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Roofing (Cont'd)				
A	100x50mm collars	LM		28	
B	150x50mm timber beam bolted to top of pipes (M/S)	LM		33	
C	75x50mm purlins	LM		102	
D	28 gauge aluminium pre-painted roofing sheets nailed to purlins (M/S)	SM		96	
E	Matching ridge caps	LM		17	
F	100mm diameter CHS encased in concrete at the base	LM		29	
G	250mm girth x 100mm wide x 5mm thick "U" shaped plate welded to top of pipe	NO		18	
H	100mm rainwater gutters	LM		25	
I	5000 litre plastic water tank as "ROTO" or equal and approved, complete hard stand, taps and any other necessary plumbing works.	ITEM		1	
	CARRIED TO COLLECTION				

PROPOSED KITUMBINI CATTLE DIP

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>PRE-DIPPING & POST DIPPING AREAS:-</u>				
A	150x150mm treated hardwood 1800mm high morticed in concrete at the bottom.	NO	54		
B	25x200mm deep hardwood treated timber nailed to ditto	LM	263		
C	1925X1800mm high hardwood gates.	NO	3		
D	Excavate pit, 1.2m wide and 3.0m depth, provide all materials and construct a humus pit complete with cover slab and manhole cover.	ITEM	1		
E	Provide potable water, fill the dipping tank and test for leakages	ITEM	1		
F	Allow for provision of acaricides as directed by the project manager.	ITEM	1		
CARRIED TO COLLECTION					

PROPOSED KITUMBINI CATTLE DIP

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	COLLECTION				
A	Brought forward from Page 1				
B	Brought forward from Page 2				
C	Brought forward from Page 3				
D	Brought forward from Page 3				

PROPOSED KITUMBINI CATTLE DIP

CARRIED TO GRANDSUMMARY					
ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<u>PROVISIONAL SUMS</u>				
A.	Provide a Provisional Sum of Kenya Shillings Two Hundred Thousand (Kshs.200,000.00) for Contingencies	SUM			
B	Provide a Provisional Sum of Kenya Shillings One Hundred Thousand (Kshs.100,000.00) for Management.	SUM			

PROPOSED KITUMBINI CATTLE DIP

CARRIED TO GRANDSUMMARY			
ITEM	DESCRIPTION	OFFICIAL	TENDERER
1	PRELIMINARIES		
2	TOTALS OF BUILDER'S WORK		
3	PROVISIONAL SUMS		
	SUB TOTAL		
	ADD 16% V.A.T. (on Items 1. and 2. above)		
TOTAL EXPENDITURE TAKEN TO FORM OF TENDER			

Amount in words, Kenya
Shillings.....

Tenderer's Signature and stamp.....

Addresses.....

Date.....

Tenderer's Signature and stamp.....

Addresses.....

Date.....