

**BILL OF QUANTITY
FOR
SIYU WATER PROJECT**

BILL (A) – CONSTRUCTION OF 11.534KM PIPELINE

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
1.0	<p><u>Clearing of pipeline route</u> Clear pipeline route of bushes, undergrowth, trees, debris and rubbish and dispose. Width of clearance to be 2.0m to accommodate for access road and trench and excavation of materials.</p> <p><u>Excavation</u></p>	M	11,534		
1.1	Excavate for pipe trench to a depth not exceeding 1000mm for 100mm diameter Pvc pipes, prepare bed on completion of excavation.	M	760		
1.2	Excavate for pipe trench to a depth not exceeding 1000mm for 80mm diameter Pvc pipes, prepare bed on completion of excavation.	M	520		
1.3	Excavate for pipe trench to a depth not exceeding 1000mm for 50mm diameter Pvc pipes class D, prepare bed on completion of excavation.	M	2,040		
1.4	Excavate for pipe trench to a depth not exceeding 1000mm for 25mm diameter Pvc pipes class D, prepare bed on completion of excavation.	M	972		
1.5	Excavate for pipe trench to a depth not exceeding 1000mm for 20mm diameter Pvc pipes class D, prepare bed on completion of excavation.	M	5,064		
1.6	Excavate for pipe trench to a depth not exceeding 1000mm for 20mm diameter PPR pipes class D, prepare bed on completion of excavation.	M	2,178		
	<i>SUB-TOTAL</i>				

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
	<u>Laying and jointing of pvc pipes.</u>				
1.7	Distribute, lay and joint 100mm diameter Pvc pipes class D in trench including making provisions for appurtenances and pipe fittings as per specifications.	M	760		
1.8	Distribute, lay and joint 80mm diameter Pvc pipes class D in trench including making provisions for appurtenances and pipe fittings as per specifications.	M	520		
1.9	Distribute, lay and joint 50mm diameter Pvc pipes class D in trench including making provisions for appurtenances and pipe fittings as per specifications.	M	2,040		
2.0	Distribute, lay and joint 25mm diameter Pvc pipes class D in trench including making provisions for appurtenances and pipe fittings as per specifications.	M	972		
2.1	Distribute, lay and joint 20mm diameter Pvc pipes class D in trench including making provisions for appurtenances and pipe fittings as per specifications.	M	5,064		
2.2	Distribute lay and joint 20mm diameter PPR pipes for meter installation.	M	2,178		
	<u>Backfilling</u>				
2.3	Backfill trench using well selected excavated material after laying and jointing the 100mm, 80mm, 50mm, 25mm and 20mm PVC and PPR pipes.	M	11,534		
	<i>SUB-TOTAL</i>				

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
2.4	<u>Installation of 363 Consumer Water Meters</u> Distribute and install 363No. of 15mm Kent Water Meters as directed by the Engineer.	No.	363		
2.5	<u>Road crossing</u> Allow for provision of road crossing; culvert construction and casing for PVC pipes.	Lump sum	1		
2.6	<u>Construction of valve chambers</u> Construct standard reinforced concrete valve chambers. Include for hardcore fill, boxing out for manhole and fixing of 1No. MS manhole cover and frame light duty 600x 450mm for water master meters, air valves and washout.	No.	20		
2.7	<u>Pressure Testing & Disinfection.</u> Allow for carrying out pressure testing on pipeline.	M	4,292		
2.8	<u>Installation of Air Valves, Wash out and Water Master Meters.</u> Install rising air valves wash out and water master meters and connect to pipeline as instructed on site.	No.	20		

	<i>SUB-TOTAL</i>				
--	-------------------------	--	--	--	--

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
2.9	<u>Installation water master meters.</u> Provide and install 2" water meters at inter connection of the 80mm diameter PVC Pipeline.	No.	3		
3.0	<u>Construction of interconnection chambers.</u> Supply all materials, construct chambers for interconnection of the gravity main of 80mm diameter and the extension distribution mains of 50mm	No.	5		
3.1	Install and connect to pipeline sluice valve and all other fittings.	No.	2		
3.2	<u>Miscellaneous</u> Provide concrete class 15 include for the required formwork and additional excavation for anchor blocks and surrounding of pipeline as directed by the Engineer (Provisional).	No.	16		
3.3	<u>Mark post</u> Provide, lay and fix in place and paint pre-cast reinforced concrete marker posts along the pipeline at 200m interval, the posts to be with letter 100mm, 80mm and 50mm posts be painted blue. The size to be 75mm x100mm x 150mm long.	No.	33		

	TOTAL				
--	--------------	--	--	--	--

BILL (B) – MATERIALS FOR PIPELINE					
Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
1.	PVC 100mm Diameter pipes class D	No.	127		
2.	PVC 80mm Diameter pipes class D	No.	87		
3.	PVC 50mm Diameter pipes class D	No.	340		
4.	PVC 25mm Diameter pipes class D	No.	162		
5.	PVC 20mm Diameter pipes class D	No.	844		
6.	PPR 20mm Diameter pipes class D	No.	363		
7.	PVC Tee 80mm Diameter Tee	No.	5		
8.	PVC 80mm Diameter Adaptor (male threaded)	No.	10		
9.	PVC 4" x 3" Reducing socket	No.	12		
10.	PVC 3" x 2" Reducing socket	No.	9		
11.	G.I. 1 meter pipe Heavy class 3" (one end to be flanged and the other end threaded).	No.	16		
12.	G.I. 2 meter pipe 2" (one end flanged and the other end threaded).	No.	24		
13.	PVC Tee 2"	No.	30		
14.	PVC 2" x 1" Reducing socket	No.	12		
15.	PVC 1" Tee	No.	74		
16.	PVC 1" x 3/4" Reducing socket	No.	86		
17.	PVC 3/4" Tee	No.	268		
18.	PVC 3/4" Adaptor	No.	363		
19.	PVC 3" Adaptor	No.	12		

	<i>SUB-TOTAL</i>				
--	-------------------------	--	--	--	--

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
20.	G.I 3" Socket	No.	60		
21.	PVC 1" Adaptor	No.	100		
22.	G.I 3/4" Plain socket	No.	1,089		
23.	G.I 3/4" Elbow	No.	1,452		
24.	G.I 3/4" Bend	No.	726		
25.	Water Meter (Kent) 1/2"	No.	363		
26.	G.I 3/4" x 1/2" Reducing Bush	No.	1,089		
27.	Tap (Pegler) 1/2"	No.	363		
28.	Thread seal	No.	1,000		
29.	Solfix cement	LTR.	100		
30.	Sluice valve 3"	No.	7		
31.	Gate valve 2"	No.	42		
32.	Gate valve 1"	No.	50		
33.	Gate valve 3/4"	No.	726		
38.	G.I Nipple 3/4"	No.	116		
39.	G.I Plain Socket 3/4"	No.	363		

	<i>SUB-TOTAL</i>				
--	-------------------------	--	--	--	--

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
	<u>MATERIALS FOR VALVE CHAMBERS.</u>				
1.	Water meter 3" (Kent) Flanged	No.	2		
2.	Water meter 2" Flanged	No.	1		
3.	Air valve 3" Female screwed	No.	1		
4.	Air valve 2" Female screwed	No.	10		
5.	Gate valve 2" U.K	No.	10		
6.	G.I Nipple 2"	No.	10		
7.	G.I Plain socket 2"	No.	20		
8.	G.I Tee 2"	No.	6		
9.	G.I Tee Flanged 3" (both sides)	No.	1		
10.	G.I Plain socket 3"	No.	24		
11.	PVC Adaptor 3"	No.	2		
12.	G.I Nipple 3"	No.	1		

	<i>SUB-TOTAL</i>				
Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
13.	G.I Flange 3"	No.	10		
14.	PVC Reducing Socket 3" x 2"	No.	10		
15.	Bolts, Nuts and Washers of 16mm Diameter of 3" length	No.	220		
16.	Bolts, Nuts and Washers of 10mm Diameter of 3" length	No.	200		
17.	Gaskets 6mm thickness	Kg	10		
18.	PVC Adaptors 2"	No.	20		
19.	G.I Nipple 2"	No.	1		
20.	Coral Blocks 9" x 9" x 16"	No.	2,400		
21.	Portland Cement	Bag.	180		
22.	Building Sand	Tonne	18		
23.	Ballast	Tonne	54		
24.	Provide for pre-cast reinforced cover for 8No. valve chambers	Lump Sum	1		

	MATERIALS TOTAL				

BILL (C) – CONSTRUCTION OF 50M³ SUMP TANK

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<u>Site Clearance</u>				
1.0	Clear tank site of all bushes, scrubs, undergrowth and trees and remove all stumps and roots and dispose.	Lump Sum	1		
1.1	Excavate tank site commencing from 200mm below ground level but not exceeding 1.5m deep.	M ³	60		
1.2	Ditto 1.5m to 3.0m deep.	M ³	20		
1.3	Provide, place and compact 200mm thick hardcore as shown on the drawings.	M ²	40		
1.4	Provide, place 50mm thick blinding 1:3:6 concrete mix on top of hardcore and compact.	M ²	40		
1.5	Provide, mix and place 250mm thick vibrated reinforced concrete 1:2:4 mix to floor slab. Allow for curing.	M ³	10		
1.6	Provide, mix and place 1:3 cement sand screed 20mm thick on top of floor slab. Allow for curing.	M ²	38		
1.7	Provide, place and joint 250mm thick dressed coral stone tank wall in 1:3 cement sand mortar as directed by the engineer.	M ²	37		
1.8	Provide, prepare and apply 1:3 cement sand plaster of 25mm thick to internal sides of tank wall. Allow for water proof cement and curing.	M ²	37		

	<i>SUB-TOTAL</i>				

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
1.9	Provide, prepare and apply 1:3 cement sand plaster of 20mm thick to external sides of tank wall. Allow for curing.	M ²	37		
	<u>Reinforcement</u>				
2.0	Provide and fix R8 reinforcement bars in horizontal mortar joint of tank wall as shown on drawing.	M	400		
2.1	Provide and fix Y10 reinforcement bars in concrete foundation of tank bottom as shown on drawings directed by engineer.	M	856		
2.2	Provide and fix Y10 reinforcement bars in concrete roof slab of the tank as shown on the drawing.	M	887		
2.3	Provide a ventilation of 100mm diameter using G.I bends on the roof slab of the tank and fix gauge wire as diameter on site.	No	4		
2.4	Provide and fix all the piping system of inlet, outlet, washout and all other necessary fittings of the tank as directed on site.	Lump sum	1		
2.5	Provide materials for construction of valve chamber at inlet and outlet of tank.	No	2		

	<i>SUB-TOTAL</i>				

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	<i>Balance Brought Forward</i>				
	<u>Sundries</u>				
2.6	Provide, mix and place reinforced concrete 1:2:4 to column as shown on the drawings. Allow for plastering. The column size to be 200 x 200mm.	No.	2		
2.7	Provide a manhole opening of size 600mm x 600mm on top of roof with a lockable cover.	No.	1		
2.8	Provide, erect and fix Y10 bar on the floor slab for the columns as shown on the drawings.	M	24		

	TOTAL				

BILL (D) - FABRICATION & INSTALLATION OF 24M ELEVATED TANK					
Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
1.0	<u>Excavation and earthworks.</u> Excavate for foundation to a depth not exceeding 1500mm.	Item	1		
1.2	<u>Tank construction.</u> Construct a 50m ³ METRIC COLD Pressed Steel Sectional Water Storage Tank of size 5000mm x 5000mm x 2000mm to BS 1564 Part II complete with 1.5mm thick pitched roof cover, Internal & External ladders, Water Level Indicator, Vent Cleats, Stays, Manhole with lockable cover, Glasticord joining compound, galvanized nuts, bolts & washers. Tank painted with 2 coats Bituprime internally & Aluminium paint externally – Plate thickness 4.5mm.	No.	1		
1.3	Provide 15m high Tank tower to BS 449 complete with walk way, hand rail, ladder painted with 2 coat of Aluminium paint.	No.	1		
1.4	Fabricate and erection of structural steel work for 15m steel tower.	Item	1		
1.5	Allow for piping costs and transportation to site.	Item	1		

	TOTAL				

BILL (E) – INSTALLATION OF SOLAR PUMPING SYSTEM

Item No.	Description	Unit	Qty.	Rate	Amount (Kshs.)
	Supply and install a solar pump for pumping water from a 10m deep well to a 15m high 50m ³ water tower. Consider a 45m total head and 50,000 litres daily water requirement.				
1.	Lorentz PU4000 C-SJ8-15pump c/w motor PS4000 4kVA DC pump controller	No.	1		
2.	PV Disconnect switch 440v/40A	No.	1		
3.	Well-probe sensor	No.	1		
4.	Solarworld 85w 12v Solar modules	No.	1		
5.	Solarworld cable dual core	No.	42		
6.	Surge Protector PS4000	M	100		
7.	4mm ² 4core submersible cable	No.	1		
8.	Cable joint (1.5mm-4mm)	M	100		
9.	Pressure KIT Switch	No.	2		
10.	Dayliff 1½” 3m pipe	No.	1		
11.	Dayliff 1½” adaptor set	No.	7		
12.	Solar support structure	No.	1		
13.	Installation materials	LS.	1		
14.	Installation Labour & Transport	LS.	1		
15.	Fencing chain link and securing the solar	LS.	1		
16.	system and the well.	SM.	5		

	TOTAL				

GENERAL SUMMARY OF BILL OF QUANTITY FOR SIYU VILLAGE

BOQ ITEM.	DESCRIPTION	AMOUNT (KSHS)
BILL (A)	CONSTRUCTION OF 11.534KM PIPELINE	
BILL (B)	MATERIAL FOR 11.534KM PIPELINE	
BILL (C)	CONSTRUCTION OF 50M ³ SUMP TANK	
BILL (D)	CONSTRUCTION OF 24M STEEL ELEVATED TANK	
BILL (E)	INSTALLATION OF SOLAR PUMPING SYSTEM	
	<i>SUB - TOTAL</i>	
	CONTINGENCY (5%)	
	GRAND TOTAL	

**PROFILE DRAWINGS
FOR
SIYU WATER PROJECT**


Alignment 2 INCH PIPE TO SIYU FORT PROFILE

- NOTES
- Excavation of trench the design depth shall be greater or equal to 1000mm unless instructed by Site Engineer.
 - CP stand for Control Point.
 - TM stand for Temporary Bench Mark.

MINISTRY OF ENVIRONMENT WATER AND NATURAL RESOURCE COUNTY GOVERNMENT OF LAU
LAU COUNTY
PROJECT: FIZA WARD WATER PROJECT
(LAU EAST SUB COUNTY)

DRAWING TITLE: 2 INCH PIPELINE LONGITUDINAL PROFILE

SCALE: AS SHOWN



SIN VALU

SIN BN COUNTY OFFICER


SIN BN JAMASO MANAGING DIRECTOR

CHECKED BY: TECHNICAL MANAGER
JACOB CHODIPA
DATE 7-01-2019

DRAWN BY: JX GTAU
DATE 7-01-2019
SIN

SURVEYED BY: JX GTAU
DATE 22-10-2018
SIN

Alignment 2 INCH PIPE COUNTY WATER STATION - SIYU SECONDARY PROFILE



NOTES

- Elevation of trench the depth shall be greater or equal to 1000mm unless instructed by Site Engineer.
- 0+000 is for Control Point.
- TBM started for Temporary Bench Mark.

MINISTRY OF ENVIRONMENT WATER AND NATURAL RESOURCES
GOVERNMENT OF LAMU
LAMU COUNTY
PROJECT FAZA WASH WATER PROJECT
(LAMU EAST SUB COUNTY)

DRAWING TITLE: 2 INCHES PIPELINE LONGITUDINAL PROFILE

SCALE AS SHOWN

SPV VILLAGE

SIN RY COUNTY OFFICER

SIN RY LAMUSO MANAGING DIRECTOR

CHECKED BY: TECHNICAL MANAGER
JACOB GADOMPA
DATE: 7-01-2019

DESIGNED BY: J.A. OTU
DATE: 5-01-2019

SUPERSED BY: J.A. OTU
DATE: 23-10-2018

Alignment 3 INCH PIPE PROFILE


NOTES

- Excavation of trench the design depth shall be greater or equal to 1000mm unless instructed by Site Engineer.
- CP stand for Control Point.
- TBM stand for Temporary Bench Mark.

MINISTRY OF ENVIRONMENT WATER AND NATURAL RESOURCE COUNTY GOVERNMENT OF LAMU LAMU COUNTY
PROJECT: FAZA WARD WATER PROJECT (LAMU EAST SUB COUNTY)

DRAWING TITLE: 3 INCHES PIPELINE LONGITUDINAL PROFILE

SCALE: AS SHOWN



DRAWN BY: J.K. GITAU
DATE 5-10-2018
SIGN


CHECKED BY: TECHNICAL MANAGER
JACOB CHIZPHA
DATE 7-01-2019
SIGN

SIGN BY: LAMUSCO
MANAGING DIRECTOR
SIGN

SIGN BY: COUNTY
OFFICER
SIGN

SIYU VILLAGE

Alignment- 3 INCH PIPE PROFILE



SCALE: AS SHOWN

Siyu Village

SIGN BY: COUNTY OFFICER

SIGN BY: LAMUSO MANAGING DIRECTOR

CHECKED BY: TECHNICAL MANAGER
JACOB CHIZIPHA
DATE 7-01-2019

DRAWN BY: J.K. GITAU
DATE 5-01-2019

SURVED BY: J.K. GITAU
DATE 23-10-2018

Bill of Quantity For Siyu Village

729000

729200

729400

729600

729800

730000

730200

SIYU FORT MONUMENT

2

2 inch pipe

W.O

2

3 inch pipe

3 inch pipe

2 inc

3 inch pipe

2 inch

LAMU COUNTY WATER STATION

EXIST PUMP STATION

2 inch pipe


SIYU SECONDARY GATE

2 inch pipe

3 inch pipe

SIYU PIPE LAYOUT

PROPOSED SITE



**SUMP TANK DRAWINGS
FOR
SIYU WATER & SANITATION PROJECT**

NOTES

1. All measurements in (MM) unless otherwise stated.
2. Reinforced concrete to be 1:2:4 mix by volume.
3. Water cement concrete reinforcement mix 1:1:6.
4. Floor and roof slab shall be cast in continuous operations.
5. Surface of the concrete must be kept moist for 7 days.
6. Shuttering for the roof slab to be adjusted so that at the centre it is 30mm above top level of the tank wall.
7. Sumpcrete to remain in place for 28 days after concrete has been cast.
8. No deviation or alteration shall be made from this drawing [PLAN] without the prior consent.
9. Contractor shall read and verify dimensions before starting any work.
10. This drawing should be read in conjunction with structural drawing.
11. Foundation depth to be determined on site.
12. Any discrepancy to be notified to the project consultant at once.

CLIENT:
LANL/WATER & SEWAGE CO. LTD.


PROJECT:
PROPOSED 50M³ SNU
SUMP TANK

Checked by: Mr. Jacob M. Chatterjee

Signed by M.D.
Ms. Paul K. Williams

Structural Drawing
Layout Plans

DATE: OCT. 2018 PROJ. No.
SCALE: AS SHOWN
DESIGN BY: D. M. Raza C923802138



PLAN Scale 1:50

Sl. No.	TOTAL LENGTH (m)	SKETCH OF SHAPE
1	10.5	
2	11.2	
3	11.9	
4	12.6	
5	13.3	
6	14.0	
7	14.7	
8	15.4	
9	16.1	
10	16.8	
11	17.5	
12	18.2	
13	18.9	
14	19.6	
15	20.3	
16	21.0	21.0 (m)

CLIENT: JALVI WATER & SEWERAGE CO. LTD.

PROJECT: PROPOSED 50M³ SPTU SUMP TANKS


Checked by: Mr. Jacob M. Chidambaram

Signed by: M.D. Mr. Paul K. Varghese

TITLE: Structural Drawing Layout Plan (Sheet 2 of 4)

DATE: 1 OCT, 2018 PRG. No. ALL: AS/HC/MTS DESIGN BY: D.M. Raju (723805229)

Sl. No.	BAR MARK	NO IN EACH	LENGTH OF EACH (mm)	CUT LENGTH (mm)	TOTAL LENGTH (m)	SKETCH OF SHAPE
1	1	2	9000	9000	18.0	
2	2	4	7996.65	7996.65	31.99	
3	3	4	7996.65	7996.65	31.99	
4	4	4	8078.78	8078.78	32.31	
5	5	4	8078.78	8078.78	32.31	
6	6	4	8078.78	8078.78	32.31	
7	7	4	8078.78	8078.78	32.31	
8	8	4	8078.78	8078.78	32.31	
9	9	4	8078.78	8078.78	32.31	
10	10	4	8078.78	8078.78	32.31	
11	11	4	8078.78	8078.78	32.31	
12	12	4	8078.78	8078.78	32.31	
13	13	4	8078.78	8078.78	32.31	
14	14	4	8078.78	8078.78	32.31	
15	15	4	8078.78	8078.78	32.31	
16	16	4	8078.78	8078.78	32.31	32.31 (m)



PLAN OF TOP SLAB Scale 1:50

PLAN OF TOP SLAB Scale 1:50

CLIENT: JALVI WATER & SEWERAGE CO. LTD.

PROJECT: PROPOSED 50M³ SPTU SUMP TANKS

Checked by: Mr. Jacob M. Chidambaram

Signed by: M.D. Mr. Paul K. Varghese

TITLE: Structural Drawing Layout Plan (Sheet 2 of 4)

DATE: 1 OCT, 2018 PRG. No. ALL: AS/HC/MTS DESIGN BY: D.M. Raju (723805229)

<div>NOTES</div> <div><div>1. All measurements in (MM) unless otherwise stated.</div><div>2. Reinforced concrete to be 1:2:4 mix by volume.</div><div>3. Water cement cover over reinforcement min. 40mm.</div><div>4. Floor and roof slab to be cast in continuous operation.</div><div>5. Surface of the concrete must be kept moist for 8days</div><div>6. Shuttering for the roof slab to be adjusted so that at the center it is 30mm above top level of the tank wall.</div><div>7. Supports to remain in place for 28days after concrete has been cast.</div><div>8. No deviation or alteration shall be made from this drawing [PLAN] without client's prior consent.</div><div>9. Contractor shall read and verify dimensions before starting any work.</div><div>10. This drawing should be read in conjunction with structural drawing.</div><div>11. Foundation depth to be determined on site.</div><div>12. Any discrepancy to be notified to the project consultant at once.</div></div>	<div>CLIENT</div> <div>LAMU WATER & SEWERAGE CO. LTD</div>	<div>PROJECT</div> <div>PROPOSED 30M³ SIYU SUMP TANK</div>	<div>Checked by:</div> <div>Mr. Jacob M. Chidzipha</div>	<div>Signed by M.D:</div> <div>Mr. Paul K. Vainaina</div>	<div>TITLE:</div> <div>Structural Drawing Layout Plan (Sheet 4 of 4)</div>	<div>DATE : OCT, 2019 DRG. No.</div> <div>SCALE: A3 9-10/19</div> <div>DESIGN BY: D.M. Njira C025804208</div>
---	--	---	--	---	--	--

